



- NOTES:**
1. ALL RESIDENTIAL LOTS ON LAKES, EXCEPT FOR LOTS ON NEW DRAWING LAKES WFW-A AND WFW-B, WILL HAVE THE PROPERTY LINE YARD DRAINS INSTALLED AS SHOWN ABOVE.
 2. CONTRACTOR SHALL COMPACTED REPAIRED LAKE SLOPE TO 95% INCLUDING THE AREA AROUND THE YARD DRAIN.
 3. BERM HEIGHT AND INLET GRATE ELEVATION SHALL BE ADJUSTED TO WORK WITH EXISTING YARD GRADING TO ASSURE THAT THE SLOPES CREATED WITH THE DRAINAGE INLET INSTALLATION CAN BE MOWED.
 4. CONTRACTOR SHALL SOD ALL DISTURBED AREAS WITH FLORITAM SOD AND REPAIR IRRIGATION THAT WAS DAMAGED BY THE CONSTRUCTION.

- LEGEND:**
- LOT DRAINAGE IMPROVEMENTS COMPLETED BY CDD EMERGENCY REPAIR
 - LOT DRAINAGE IMPROVEMENT INSTALLATION IN PROGRESS BY LENNAR
 - LOT DRAINAGE IMPROVEMENTS INSTALLATION COMPLETED BY LENNAR
 - LAKE BANK & LINEAR EROSION AREAS

UPDATED: 02/10/2021

PREPARED FOR:
**BONITA BEACH ROAD
 GOLF ESTATES CDD**

NO.	DATE	REVISION DESCRIPTION	BY

BANKS ENGINEERING
 Professional Engineers, Planners, & Land Surveyors
 Serving The State Of Florida

10511 SIX MILE CYPRESS PARKWAY
 FORT MYERS, FLORIDA 33966
 PHONE: (239) 939-5490 FAX: (239) 939-2523
 ENGINEERING LICENSE # EB 6469
 SURVEY LICENSE # LB 6690
 WWW.BANKSENG.COM

EROSION REPAIR LAKE RECONSTRUCTION LEE COUNTY, FLORIDA						
DATE	PROJECT	DRAWING	DESIGN	DRAWN	CHECKED	SCALE
02/10/2021	1324L	1324L-PH1	DRU	KG	DRU	N.T.S.
						SHEET 001

S:\AR\1324\1324L\1324L-PH1\1324L-PH1.DWG 2/10/2021 4:00 PM KEVIN DONALDZ